

TO: ✓

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01255-00-00

Spot: NESENESEW

Sec/Twnshp/Rgc: 2-26S-8E

1795 feet from S Section Line, 2710 feet from E Section Line

Lease Name: STEVENSON

Well #: 5

County: GREENWOOD

Total Vertical Depth: 2432 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	6.63	2348		75 SX
------	------	------	--	-------

SURF	8.25	1650		75 SX
------	------	------	--	-------

Well Type: OIL

UTC Docket No:

Date/Time to Plug: 06/21/2018 12:00 AM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DARYL WHITEMAN

Company:

Phone: (316) 640-9072

Proposed Plugging Method: Set 50 ft cement plug at TD. Shoot casing at 1000 ft and 150 ft. set a 50 ft cement plug at 1000 ft, pull tubing to 150 ft and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/25/2018 12:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1900' hit iron in well bore, pumped 30 sxs cement, pulled tubing to 900' pumped 15 sxs cement, pulled tubing to 150', pumped 135 sxs cement to surface, gel spacers between cement plugs, casing shot @ 900' & 150',

RECEIVED
KCC DIST # 3
JUL 09 2018
CHANUTE, KS

mt

INVOICED


AUG 23 2018

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)



Cement or Acid Field Report
Ticket No. **3997**
Foreman *Rick Ladford*
Camp *Furber HS*

Job Type <u>P.T.A. old well</u>	Hole Depth _____	Slurry Vol. _____	Tubing <u>2 3/8"</u>
Casing Depth _____	Hole Size _____	Slurry Wt. _____	Drill Pipe _____
Casing Size & Wt. <u>2"</u>	Cement Left in Casing _____	Water Gal/SK _____	Other _____
Displacement _____	Displacement PSI _____	Bump Plug to _____	BPM _____

30 sks @ 1700'
15 sks @ 1800'
135 sks @ 150' to surface

"Thank you"

Get spaces between plugs

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.