

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19181-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 17-25S-5E
2771 feet from S Section Line, 2330 feet from E Section Line
Lease Name: L W ROBISON SOUTH Well #: 20 A
County: BUTLER Total Vertical Depth: 2553 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2552		65 SX
SURF	8.625	224		90 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICH CLARK/HAYS WILSO Company: _____ Phone: (405) 526-0111

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/20/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

PACKER & TUBING HUNG UP IN HOLE. RIH ON WIRELINE CUT TUBING @ 2390', LEFT PACKER IN HOLE @ 2410'. LAYED DOWN TUBING. RIH WITH TUBING @ 2390', QWS ESTABLISHED CIRCUALTION MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS & DISPLACED IN CASING. PERFROATED SQUEEZE HOLES 275'-276' (4 HOLES). RIH WITH TUBING AT 263', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO 4 1/2" CASING & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
2470	2553		CSG

INVOICED
AUG 23 2018

Remarks: COMPLIANCE LIST / OVER 10 YEARS / DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

1/1