

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-00044-00-01
Spot: SWNWSESE Sec/Twnshp/Rge: 4-19S-2W
961 feet from S Section Line, 991 feet from E Section Line
Lease Name: JOHNSON Well #: 1
County: MCPHERSON Total Vertical Depth: 3035 feet

Operator License No.: 35317
Op Name: PLUM CREEK ENERGY, LLC
Address: 604 N. BISMARK AVE
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	2965		260 SX
SURF	8.625	158		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2018 4:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: SHERRY DEWERFF Company: _____ Phone: (620) 793-4831

Proposed Plugging Method: PLUG IN ACCORDANCE WITH ICC REQUIREMENTS. USUALLY THIS CONSISTS OF CIBP OR A 50' SAND PLUG AT BOTTOM COVERED WITH A 5 SACK CEMENT PLUG. FILL FROM 250' TO SURFACE WITH CEMENT (ANNULUS AND CASING). CUT CASING OFF BELOW GROUND LEVEL. RESTORE GROUND AS NEEDED.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2018 4:00 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

RAN IN AND TAGGED @ 60'. WENT IN WITH OVER SHOT AND RODS TO SPEAR PVC. THEN RAN IN WITH CUT NIPPLE ON 2 7/8" TUBING TO DRILL OUT PVC THAT WAS IN WELL. GOT DOWN TO 85' RECOVERED 1 JOINT OF PVC. RAN IN WITH 3 1/2" AND TRI-CONE BIT MILLED 8 HOURS GAINED 1 FOOT. ADDED DRILL COLLARS FOR WEIGHT AND COUNTINUED DRILLING. GOT DOWN TO 405' AFTER 8 HOURS. NO PVC CUTTINGS IN RETURNS. RAN 2 3/8" IN STOPPED AT 60' PULLED 2 3/8" RAN 1" INTO 405' (BRIDGED OFF) PULLED BACK 1 JOINT. PUMPED 120 SX 60/40 CEMENT WITH 4% GEL NO RETURNS. PULLED 1" LET STAND FOR 2 HOURS. THEN RAN IN 1' TO 350' PUMPED 130 SX AND CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2965	2985	CSG	

INVOICED
AUG 23 2018

Remarks: QES TICKET 355335. NO BOTTOM PLUG.

Plugged through: CSG

District: 02

Signed Jerry Spurling
(TECHNICIAN)

1/3