

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22188-00-00
Spot: NESWSW Sec/Twnshp/Rge: 27-19S-10W
990 feet from S Section Line, 4415 feet from E Section Line
Lease Name: HATHAWAY Well #: 1
County: RICE Total Vertical Depth: 3269 feet

Operator License No.: 7079

PROD Size: 5.5 feet: 3259 125 SX CMT

Op Name: FOX, DON

SURF Size: 8.625 feet: 228 160 SX CMT

Address: SOUTH MAIN STREET
CHASE, KS 67524

106 24

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/11/2004 11:45 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed
Plugging
Method:

See actual report.

RECEIVED
KCC DISTRICT #2

MAY 17 2004

WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/11/2004 3:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded open hole to 3200' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 1315'. Pulled to 1250' and pumped 35 sacks of cement. Pulled casing to 900' and pumped 35 sacks of cement. Pulled casing to surface -- no circulation. Ran tubing down to 800' and pumped 16 sacks of gel and 300 lbs of cotton hulls. Waited 1-1/2 hours and pumped 35 sacks of cement with 3% calcium -- got circulation. Pulled to 280' and pumped 145 sacks of cement -- got circulation to surface on 5/12/2004.

60/40 posmix with 4% gel.

5/11/2004 Allied Cement #18103

5/12/2004 Allied Cement #18104

Remarks: PLUGGED THROUGH CASING AND TUBING.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE 5-19-04
INV. NO. 20040615.71