

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21388-00-00
Spot: SWSE Sec/Twnshp/Rge: 8-27S-33W
663 feet from S Section Line, 1986 feet from E Section Line
Lease Name: FEDERAL B Well #: 1
County: HASKELL Total Vertical Depth: 5400 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

CIBP Size: feet: 5170 WITH 2 SX CMT
MSCC Size: feet: 3170 WITH 75 SX CMT
PROD Size: 5.5 feet: 5400 WITH 205 SX CMT
SURF Size: 8.625 feet: 1757 WITH 620 SX CMT

\$175⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2004 10:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT ON BOTTOM. PLUG AT 1780' WITH 50 SX CMT. PLUG AT 800' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: NONE

Date/Time Plugging Completed: 05/11/2004 11:00 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

PBTD 5170'. PUMP 400# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG PULL TO 1780' & SPOT 50 SX CMT. 2ND PLUG PULL TO 800' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5180 | 5196 | | |
| 5112 | 5135 | | |

RECEIVED
MAY 18 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2029' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
MAY 12 2004
KCC Dodge City

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 5-19-04
BILL NO. 2004061574

Form CP-23