

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21878-00-00
Spot: S2SEWSE Sec/Twnshp/Rge: 31-30S-5W
1425 feet from S Section Line, 1675 feet from E Section Line
Lease Name: LOCKHART Well #: 1
County: KINGMAN Total Vertical Depth: 3900 feet

Operator License No.: 5038
Op Name: ROBINSON ENERGY & EXPLORATION
Address: 300 W. DOUGLAS, STE 420
WICHITA, KS 67202

SURF Size: 8.625 feet: 284

#126 75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/15/2004 4:30 AM

Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: _____

Proposed Plugging Method:

See actual report...

RECEIVED
KCC DISTRICT #2

MAY 17 2004

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: NONE

Date/Time Plugging Completed: 05/15/2004 7:00 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Pulled drill pipe to 950' and pumped 35 sacks of cement. Pulled to 600' and pumped 35 sacks of cement. Pulled to 335' and pumped 35 sacks of cement. Pulled to 60' and pumped 25 sacks of cement to surface.

15 sacks of cement in rathole and 10 sacks of cement in mousehole.

60/40 posmix with 4% gel.

Remarks: ALLIED CEMENT #15324

Plugged through: DP

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE 5-19-04

BY. NO. 2004061577