

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20617-00-00
Spot: E2E2NW Sec/Twnshp/Rge: 29-17S-10W
3960 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JANSSEN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3302 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

CIBP Size: feet: 3200
PROD Size: 5.5 feet: 3293 100 SX CMT
SURF Size: 8.625 feet: 430 200 SX CMT

\$107³²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2004 10:00 AM

Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: BRIAN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2

MAY 17 2004

WICHITA, KS

Plugging Proposal Received By: DOUG LOUIS

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/13/2004 2:15 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded back perforations to 2750' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 1700'. Pulled to 1300' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 480' circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3184	3190		
3150	3156		
3140	3146		
3047	3054		
2993	2997		
2967	2973		
2963	2965		
2802	2810		

Remarks: COPELAND CEMENT #24431

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 5-19-04

INV. NO. 2004061575