

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21683-00-00
Spot: SESENW Sec/Twnshp/Rge: 12-8S-18W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CONYAC LAWRENCE Well #: 2
County: ROOKS Total Vertical Depth: 3350 feet

Operator License No.: 9126
Op Name: DREHER, RICHARD A. DBA STRIPPER
Address: 410 S MADISON
PLAINVILLE, KS 67663

PROD Size: 450 feet: 3344 w/150 sxs cmt
SURF Size: 8.625 feet: 247 w/160 sxs cmt

\$108⁸⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2004 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: RICK DREHER Company: STRIPPER OIL COMPANY Phone: (785) 434-7206

Proposed Plugging Method: Emergency plug with rig over hole - flowing well.
Ordered 250 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2600'.
Tied onto tubing - pumped 75 sxs cement with 300# hulls mixed in.
Pulled tubing to 1350' - pumped 60 sxs cement with 300# hulls mixed in.
Cement circulated to surface - flowing water stopped.
Pulled tubing - tied onto backside and pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Tied onto 4 1/2" casing with a swedge - pumped 110 sxs cement with 200# hulls mixed in.
Max. P.S.I. 300#. S.I.P. 0#.
Left swedge on well.
05-08-2004 - Topped with 17 sxs cement - cut off and capped with 3 sxs.

Perfs:

Top	Bot	Thru	Comments
3277	3280		
3160	3163		

RECEIVED
MAY 20 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Pat Staab

(TECHNICIAN)

INVOICED

DATE 5.20.04
INV. NO. 2004061578

Form CP-2/3

MAY 18 2004

BLACK PETROLEUM CO
200 W DOUGLAS #545
WICHITA, KS 67202

REPLACEMENT CARD:
#2 LAWRENCE CONYAC

12-9-1EW
SE SE NW

CONTR B&B DRILLING CO

CTY ROCKS

GEOL _____

FIELD CARROL J EXT (1/8 W)

ELV 1889 KBSPD 5/17/82 CARD ISSUED 9/16/82

IP P 21 BO & E BWPD

API 15-163-21,683

LANS 3277-80 &
3160 1/2 3163 1/2

LOG	Tops	Depth Datum
ANH		1283 - 606
TOP		2812 - 923
HEEB		3022 - 1133
TOR		3048 - 1159
LANS		3065 - 1176
BKC		3287 - 1398
MARM		3307 - 1418
CONG		3339 - 1450
LTD		3346 - 1457
RTD		3350 - 1461

INDEPENDENT OIL & G.
WICHITA, KANS.

8 5 8 247 82 1605X

DST (1) 3148-62 30-30-30-30 REC 5 M W FEW SPKS OIL TOP
TOOL SIP 717-668# FP 12-12 12-12#

DST (2) 3158-77 30-30-30-30 60 GIP REC 60 HOCMW 360
OCMW 300 WTR SIP 792-779# FP 49-160 198-321# BHT
104

DST (3) 3209-3250 30-30-45-45 REC 15 SOCM (15% OIL 2%
WTR 85% M) 60 OIL SPKD M SIP 1114-1093# FP 43-54 65-
65# BHT 106

DST (4) 3246-3291 30-30-45-45 REC 45 OCM (25% OIL 5%
WTR 70% M) SIP 976-1029# FP 54-54 54-65#

MICT - CO PF 3277-80. AC 250G SWB LD 1 1 2 BOPH (GR
30). RE-AC 1500 G SWB 3 48 BOPH ONFU 900 OIL SET
PIIG PF 3217-3220 AC 500G SWB LD 2 32 BFPH 94% WTR.

6% OIL. SET ON. 1000' FIH (100' OIL & 900' WTR). SQZ PFS.
3217-3220. SET PLUG 3168. PF 3160 1 2 - 3163 1 2. SET ON.
250' W. 50' MO. 200' GAS. AC 250 G. SWB LD BK. SWB 7 HRS
5.01 BFPH. 70% OIL. PULL PLUG. TST 10.80 BFPH (50% OIL
50% WTR). R&T. POP. P 21 BOPD & 5 BWPD. 9 1 82

CORRECTION: 10 21 82. RE-ISSUED CARD TO ADD ADD L COMP
INFO FIRST CARD TRIMMED IN ERROR

INDEPENDENT OIL & G.
WICHITA, KANS.