

6 010684

10-20.15-47-20397-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- ~~147-20,396-00-00~~

NE NW NW, SEC. 29, T. 1 S, R 18 ~~77E~~ (2)

TECHNICIAN'S PLUGGING REPORT

Operator License # 9597

Operator: One Way Inc.
Name & Address: Box 336
Wray, Colorado 80758

4950 feet from S section line

4290 feet from E section line

Lease Name Fischer Well # B-1

County Phillips 117.65

Well Total Depth 3620 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor One Way Inc. License Number 9597

Address Same

Company to plug at: Hour: 9:00AM Day: 20 Month: Oct Year: 19 89

Plugging proposal received from Howard Pecker

(company name) One Way Inc. (phone) _____

were: Perf casing at 1820' and 1280'. Order 300 sks cement 65/35 poz 8% gel and 500# hulls. 4 1/2" casing at 3619'. Perf at 3408' - 3508'.

Elev. 2233' Top Dakota 983' Anhydrite 1813'

Ran wireline to T.D. 3590' Top pf fluid at 2500'.

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 20 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing 25 sks cement then, 200 sks cement w/300# hulls. Working pres. 700# closed w/450#. Pumped down 8 5/8" 25 sks cement Max pres. 1000#. Closed w/500#.

Checked casing, cement was down 30'. 8 5/8" s.p. down 120' on November 3, 1989 filled pipe to base of cellar with Redi-mix.

Remarks: Allied Cement Co. (If additional description is necessary, use BACK of this form.)

INVOICED I () do not check to reserve this plugging.

DATE NOV 16 1989

INV. NO. 26484

10-20 JAN 19 1990

Signed Dale F. Balthazor (TECHNICIAN)

Dale F. Balthazor

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1989
CONSERVATION DIVISION
Wichita, Kansas