

Recd' KCC 1-21

6 070744 01-26-8989 API NUMBER 15- 153-20,731-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C SE SE , SEC. 25 , T 1 S, R 34 WAE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Horinek Well # B #1

Operator: Thunderbird Drilling Inc.  
Name & Address: Box 78407  
Wichita, Ks. 67278  
Burke B. Krueger

County Rawlins 138.55  
Well Total Depth 4263 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well Gas Well Input Well SWD Well O&A x

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 21 Month: Jan Year: 19 89

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Inc. (phone)

were: 8 5/8" - 323' S.P. cwc w/225 sks 60/40 Poz 2% Gel 3% Cal Cl. By Allied.

K.C. Well Elev. 3045'; Anhy 2888'; No circulation problems. Mud condition 5A viscosity;

9.6 weight; 10:4 Water loss. Spot with drill stem, circulate, mud between all plugs.

30 sks at 2910'; 100 sks w/1 C.F. at 2140'; 50 sks at 370'; Hulls. Plug at 40' w/10 sks

cement. 15 sks rathole (circulate) 205 sks 60/40 Poz 6% Gel 3% Cal Cl.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 9:00 PM Day: 21 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Ordered 255 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk C.F. Spotted with drill stem. Circulated heavy mud between all plugs. 1st plug at 2910' w/30 sks cement.

2nd plug at 2140' w/100 sks cement w/1 sk F.C. mixed in. After 4 or 5 minutes of pumping cement, did not get any returns. Hole stayed full though. Abercrombie waited 6 hrs. so cement

in 2nd plug would set up. After 6 hrs. tagged cement at 1890'. Pumped in an additional 50 sks cement at 1890' 3rd plug 50 sks of 370'. 4th plug Hulls. Plug at 40' w/10 sks cement,

Remarks: 15 sks in rathole (circulate) Cemented by Allied Cement.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(copy to client) observe this plugging.

DATE 1-30-89  
INV. NO. 23818

Signed Marion J. Schmidt (TECHNICIAN)