

4-032326

15-153-05183-00-00

10-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1959

SE NE SE /4 SEC. 17, 01, 34 W
1650 feet from S section line
330 feet from E section line

Operator license# 30606

Lease: Cahoj Well # 44

Operator: Murfin Drilling Company, Inc

County: Rawlins 140.73

Address: 250 N. Water - Suite #300
Wichita, Kansas 67202

Well total depth 4330 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 450 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 23 Month: October Year: 1998

Plugging proposal received from: John Turner

Company: Murfin Drilling Company, Inc. Phone: -

Were: Order 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 11:00 A.M., Day: 23 Month: October Year: 1998

Actual plugging report: 8 5/8" set at 450' w/300 sxs cwc. 5 1/2" set at 4329' w/250 sxs. P.B.T.D. 4294'. Prod. Perfs 4077' - 4268'. Squeezed 5 1/2" with 225 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 100#. Squeezed 8 5/8" with 6 sxs cement blend to Max. P.S.I. 500#. Close in P.S.I. 500#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)

11-13-98
60344

11-9-98