

6030120

15-153-05237-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____
NW, Sec. 17, T 1 S, R 34 (W) X
2310 feet from N/X section line
2310 feet from W/X section line
Lease Name Cahoj Unit Well # 36
County Rawlins
Well Total Depth 4357 feet 141.60
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 6237

Operator: Getty Oil Co.
Name & 2705 Vine Street
Address Unit #4
Hays, Kansas 67601

913-628-1039

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Oberlin, Kansas

Company to plug at: Hour: _____ Day: 30 & 31 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Getty Oil Co. Engineers

(company name) Getty Oil Co. (phone) _____

were: Run 2 3/8 Tubing to 4311' Pump 40SX. Cem. mix. Pull 600' of tubing-let cem.
mix set 3 hrs. Tag with wire line - Pump gel. to 390' lay down pipe to 390' - pump
cement to surface lay down pipe pump 2SX. Halls and 35SX. cem. mix. Down 8 5/8 /
5 1/2 annular space. Well had been squeezed previously at 1960' and 1892' Cem. mix.
> 50/50 poz 6% gel 3%cc

Signed Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11 A.M. Day: 31 Month: Jan. Year: 1984

ACTUAL PLUGGING REPORT As above

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Carl Goodrow
(TECHNICIAN)

DATE 2-8-84

FEB 06 1984

FORM CP-2/3
Rev. 9-82 9

INV. NO. 0131

CONSERVATION DIVISION
Wichita, Kansas

2-6-84

1-31