

To: 6 031025
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 03317

Operator: Beard Oil Co.
Name & Address Box 309
McCook, Neb. 69001

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____
Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 17 Month: Dec Year: 19 87

Plugging proposal received from John Mondero

(company name) Beard Oil (phone) _____

were: 8 5/8" set at 240' w/200 sks cwc. 4 1/2" set at 4330' w/200 sks, PBTD 4135',

Perfs 4116' - 4258'. Improperly plugged Oct. 8, 1987 without notification to state.

Drilled out and replugged Dec 17, 1987. Order 150 sks Econolite Cement Blend 65/35 Poz 10 % Gel 2% Dical 5 sks Hulls. Halliburton Cement Co. Water in swab tank.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 17 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Bottom cemented with 15 sks cement. 50/50 Poz 2% Gel to 4075'

casing. Free point at 750'. Shots taken at 1450' and 750'. Recovered Hole. Re-entered to 3000' with cement circulated to surface through tubing w/8 5/8" squeezed w/300# Psi. Close in. Plug complete.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
01-18-1988
JAN 18 1988

CONSERVATION DIVISION
Wichita, Kansas

DATE 1-20-88

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

WV. NO. 195-89