

6 031350

4-18 15-53-20749-00-00 234 P

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

NE NW SE, SEC. 36, T 1 S, R 34 W/ES

2310 feet from S section line

1650 feet from E section line

Lease Name Dozbaba Rummel Well # 1

County Rawlins 138.94

Well Total Depth 4275 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 30129  
Eagle Creek Corp

Operator: Name & Address  
617 N. Broadmoor  
Wichita, Ks. 67206

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 18 Month: April Year: 19 90

Plugging proposal received from Bill

(company name) Kelso (phone)

were: 8 5/8" set at w/ sks. 4 1/2" set at 4273 w/125 sks. Perf 4083 -86.

Order sand and common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel 2% dicel, 500#-hulls, Halliburton Cement Co. Larue water hauler.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:45AM Day: 18 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Dump sand on bottom to 4220 w/4 sks cement on sand w/bailer. One shot recovered 2600' of 4 1/2" casing. Sq 8 5/8 casing w/225 sks cement blend w/500# hulls mixed into max psi 300#. Close in psi 200#.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-7-90

INV. NO. 28040

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow