

15-153-05165-00-00

6 031404

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NW SE SW, SEC. 17, T 1 S, R 34 W/Ex

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line
3630 feet from E section line
Cahoj Unit #52

Operator License # 3911

Lease Name Mary Depe Well # 2

Operator: Rama Operating co. Inc.
Name & Address Box 159
Stafford, Ks. 67578

County Rawlins 143.09

Well Total Depth 4403 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 21 Month: August Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) _____

were: 8 5/8 set at 367 w/300 sks cwc. 5 1/2 set at 4403 w/250 sks.

Perf 4138 - 4322. Order 300 sks 65/35poz 8% gel 500 lbs. hulls. Allied Cement Co.

Larue water trucks. Order sand common cement. Pull pipe.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:00 PM Day: 21 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 4080 w/5 sks common cement on sand w/bailer

Recovered 1500 of casing. Laid out two joints 5 1/2 casing, tied on to 5 1/2 casing
Tied onto 5 1/2 casing. PUmpeD 125 sks cement blend to load hole. Laid down 5 1/2 casing.

Tied on to 8 5/8 casing and sq w/total of 4 sks gel and 300 sks cement blend w/400 lbs.

hulls mixed into max psi 300 lbs. Close in psi 150 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____
(If additional description is necessary, use BACK of this form.)

OCT 27 1990
10-3-90

INVOICED

DATE 10-8-90

INV. NO. 29567

Sub-5

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow