

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Apollo Energies, Inc  
Address: 10378 N 281 Hwy  
Phone: (620) 672-9001 Operator License #: 30481  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: ~~10-6-2003~~ 9-29-2003 (Date)  
by: Steve Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Simpson Depth to Top: 4504 Bottom: 4506 T.D. 4530  
Mississippi Depth to Top: 4243 Bottom: 4266 T.D. 4530  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-151-20,039 00-01  
Lease Name: W.D. Georgia WD  
Well Number: 1  
Spot Location (QQQQ): C - NE - SW -  
1980 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
Sec. 34 Twp. 28 S. R. 12  East  West  
County: Pratt  
Date Well Completed: ~~5-1985~~  
Plugging Commenced: 10-7-2003  
Plugging Completed: 10-13-2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Simpson	Oil	0	378	8 5/8	378	-0-
4504-4506	Prod	0	4529	5 1/2	4529	2810
Mississippi	Oil					
4243-4266						

RECEIVED  
MAY 19 2004  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Sand back to 4190', dump 5 sxs Portland cement on top with bailer.  
Tied onto 8 5/8" casing, pumped 300# hulls, 10 sxs gel, 50 sxs cement, 10 sx gel, 100# hulls, 8 5/8" Wiper plug, 100 sxs cement.  
Cement blend 60/40 Poz, 6% gel by Allied Cementing

Name of Plugging Contractor: Quality Well Service License #: 31925  
Address: 401 Wst Main, Lyons, Kansas 67554

Name of Party Responsible for Plugging Fees: Apollo Energies, Inc.  
State of Kansas County, Pratt, ss.

Scott Alberg (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
(Address) 10378 N. 281 Hwy, Pratt, Kansas 67124



SUBSCRIBED and SWORN TO before me this 18th day of May, 2004  
Kedzie L. Ratcliff My Commission Expires January 10, 2008  
Notary Public