

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Apollo Energies, Inc

Address: 10378 N 281 Hwy

Phone: (620) 672-9001 Operator License #: 30481

Type of Well: Oil & Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8-6-2003 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Simpson Depth to Top: 4532 Bottom: 4540 T.D. 4620
Mississippi Depth to Top: 4247 Bottom: 4255 T.D. 4620
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-21699-00-00

Lease Name: Rolf

Well Number: 1

Spot Location (QQQQ): NE - SW - NE -

3630 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 35 Twp. 28 S. R. 12 East West

County: Pratt

Date Well Completed: 10-18-1985

Plugging Commenced: 10-20-2003

Plugging Completed: 10-21-2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Simpson</u>	<u>Oil</u>	<u>0</u>	<u>423</u>	<u>8 5/8</u>	<u>423</u>	<u>-0-</u>
<u>4533-4536</u>	<u>Oil</u>	<u>0</u>	<u>4587</u>	<u>5 1/2</u>	<u>4587 4545</u>	<u>2760</u>
<u>Mississippi</u>	<u>Oil</u>		<u>4545</u>			
<u>4247-4253</u>						

RECEIVED
MAY 19 2004
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back to 4132', dump 5 sxs Portland cement on top with bailer.

Tied onto 8 5/8" casing, pumped 300# hulls, 10 sxs gel, 50 sxs cement, 100# hulls, 8 5/8" Wiper plug, 100 sxs cement.

Cement blend 60/40 Poz, 6% gel by Allied Cementing

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 401 Wst Main, Lyons, Kansas 67554

Name of Party Responsible for Plugging Fees: Apollo Energies, Inc.


State of Kansas County, Pratt, ss.

Scott Alberg (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) 10378 N. 281 Hwy, Pratt, Kansas 67124



SUBSCRIBED and SWORN TO before me this 18th day of May, 2004
Kedzie L. Ratcliff My Commission Expires January 10, 2008
Notary Public