

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,808-00-00

LEASE NAME Werth B

WELL NUMBER 1

4950 Ftt. from S Section Line

2970 Ftt. from E Section Line

SEC. 18 TWP. 13 RGE. 21 (E) or (W)

COUNTY Trego

Date Well (Completed) 1-7-1986

Plugging Commenced 4/20/04

Plugging Completed 4/20/04

RECEIVED

MAY 17 2004

KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Encore Operating Company

ADDRESS 1601 Blake St., Suite 500 Denver, CO

PHONE# (303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 4/20/04 (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? no

Producing Formation Marmatow Depth to Top 3930 Bottom 3970 T.D. 4062

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing	0	247	8 5/8	247	none
	Producing Casing	0	4060	5 1/2	4060	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Ran 2" tubing to 3000', pumped 400#'s of hulls and 140 sacks of 60/40 POS w/10% gel cement down the tubing. Circulated fluid to surface, pulled 1500' of tubing and pumped 200#'s of hulls and 120 sacks of cement to surface. Pulled tubing and pumped 25 sacks of cement down the 5 1/2" casing at 500#'s ISIP 500#'s. Pumped 20 sacks of cement down the 8 5/8" casing @ 500#'s, cement in the 5 1/2" casing is from 0 to 3930', plug down @ 12:30 p.m.

Name of Plugging Contractor Chite's Well Service Allied Cement Co License No. 99996 32028

Address Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Company

STATE OF Colorado COUNTY OF Denver, s.s.

Roland Nyp

(Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN STOCKTON KS

AND SWORN TO before me this 7th day of May, 2004

Steve R Nyp
Notary Public



My Commission Expires: 9-30-04