

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
3 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-21,537-00-00

LEASE NAME Barber

WELL NUMBER #2

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 4 TWP. 20 RGE. 10W (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-28-04

Plugging Completed 4-29-04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mike Kelso Oil, Inc.

ADDRESS P.O. Box 467 Chase, Kansas 67524

PHONE#(620) 938-2948 OPERATORS LICENSE NO. 31528

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-19-04 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3928'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf Prod</u>				<u>8-5/8"</u>	<u>209'</u>	<u>None</u>
				<u>5-1/2"</u>	<u>3437'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3320' and 5 sacks cement. Ran 2" tubing down 5-1/2" casing to 1300', pumped 35 sacks cement w/100# hulls, pulled up to 900', pumped 35 sacks cement with 100# hulls, pulled up to 260' and circulated 50 sacks to the surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike Kelso Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 7th day of May, 20 04

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CC  
Revised 05-

RECEIVED

MAY 10 2004

KCC WICHITA