

ATE OF KANSAS
ATE CORPORATION COMMISSION
J S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-159-01442-00-00
API NUMBER Comp. 10-1-40

LEASE NAME Karber

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from 5 Section Line

330 Ft. from 2 Section Line

SEC. 7 TWP. 19 RGE. 10W (E) or (W)

COUNTY Rice

LEASE OPERATOR HOFFMAN OIL, INC.

ADDRESS 18368 Lawrence 2100 Mt. Vernon, MO. 60572

PHONE#(417) 466-7022 OPERATORS LICENSE NO. 30681

Date Well Completed 11-13-1940

Character of Well Oil

Plugging Commenced 4-29-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-3-04

The plugging proposal was approved on 10-7-03 (date)

By Ralph Tittel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf.</u>				<u>8-5/8"</u>	<u>169'</u>	<u>None</u>
<u>Prod.</u>				<u>5-1/2"</u>	<u>3349'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Bridge @3350', dumped sand on top of bridge to 3270' and dumped 5 sack cement on top with bailer. Perforated 5-1/2@1250', 900' and 220'. Ran tubing to 1250', pumped 50 sacks cement, pulled tubing to 900', pumped 50 sacks cement, pulled up to 220' and circulated 45 sacks cement to surface. Pulled tubing out, tied onto 5-1/2", pumped 80 sacks cement, didn't circulate, pumped 100 more sacks cement and circulated up 8-5/8" surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hoffman Oil, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED SUBSCRIBED AND SWORN TO before me this 7th day of May, 20 04

MAY 10 2004

KCC WICHITA My Commission Expires:



Notary Public

Form CR Revised 05-