

STATE CORPORATION COMMISSION OF KANSAS
 OIL & GAS CONSERVATION DIVISION
 130 S. MARKET, - ROOM 2078
 WICHITA, KANSAS 67202-3802

API NUMBER 15-055-20666 00-02
 LEASE NAME Carr
 WELL NUMBER 2-2

 _____ 1650 feet from N/S Section Line
 _____ 2310 feet from E/W Section Line
 SEC 2 TWP 23S RGE 31W
 COUNTY FINNEY
 Date Well Completed 3-28-1995 (Per 15-13-04)
 _____ ~~08-03-1986~~
 Plugging Commenced 03-29-2004
 Plugging Completed 03-31-2004 (Per Alan Edwards)
 Producing Formation Topeka
 Depth to Top 3885'
 Depth to Bottom 3978'
 T.D. 4897'

WELL PLUGGING RECORD K.A.R.-82-3-117

Type or Print Notice: Fill out completely and return to Cons Div office within 30 days

Lease Operator PETROSANTANDER (USA) INC
 Address 6363 Woodway #350
Houston, Texas 77057
 Phone 713-784-8700
 Operators License 32198
 Character of Well Water supply (Oil, Gas, D&A, SWD, Water Supply)
 The plugging proposal was approved on 03-29-2004 (date)
 by Kevin Strubbe (KCC District Agent's Name)
 Is ACO-1 filed? Enclosed

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	472'	8-5/8"	existing	None
		Surface	4873'	5-1/2"	existing	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Filled with 300# hulls, 1st Plug @ 3978' w/35 sks, mixed w/ 100# hulls, 13 sks gel

 2nd Plug @ 2200' w/265 sks

 Top off w/75 sks mixed w/ 100# hulls

 Total 375 sks 60-40 Poz 12% gel, w/ 500# hulls

RECEIVED
 APR 23 2004
 WICHITA

Name of Plugging Contractor Allied Cementing Co License No. 99996 NA
 Address PO Box 31, Russell,, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROSANTANDER
 STATE OF TEXAS COUNTY OF HARRIS, ss.
JASON SIZEMORE (Employee of Operator) or (Operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature _____ Address 6363 Woodway #350, Houston, Texas 77057

SUBSCRIBED AND SWORN TO before me this 20th day of APRIL, 20 04

Notary Public Alan Edwards
 My Commission Expires Sept 19 / 2007

