

STATE OF KANSAS
STATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-22188-00-00

LEASE NAME Hathaway

WELL NUMBER 1

990 Ft. from S Section Line

4415 Ft. from E Section Line

SEC. 27 TWP. 19 RGE. 10W (E) or (W)

COUNTY Rice

Date Well Completed 7-20-1987

Plugging Commenced 5-10-04

Plugging Completed 5-12-04

RECEIVED

MAY 19 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DON FOX

ADDRESS P.O. Box 446 Chase, Kansas 67524

PHONE# (620) 727-2873 OPERATORS LICENSE NO. 7079

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-14-04 (date)

Virgil Clothier (KCC District Agent's Name)

ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3269'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf</u>				<u>8-5/8"</u>	<u>228'</u>	<u>None</u>
<u>Prod</u>				<u>5-1/2"</u>	<u>3259'</u>	<u>1315'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3200' and 5 sacks cement. Cut casing loose @1315', pulled up 1250', pumped 35 sacks cement w/200# hulls, pulled up to 900', pumped 200# hulls w/20 bbls. Saltwater, pumped 600# hulls w/20 bbls. saltwater, pumped 100 sacks cement w/14 bbls. saltwater. Layed rest of casing down. Ran 2-3/8" tubing to 800', pumped 16 sacks gel w/300# hulls and 35 sacks cement, pulled tubing to 300' and circulated 145 sacks cement to surface. 60/40 pos, 4% gel Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Don Fox

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of May, 2004

[Signature]
Notary Public

My Commission Expires:

