

RECEIVED
 JAN 21 1989
 01-27-1989
 CONSERVATION DIVISION
 Wichita, Kansas

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 780407, Wichita, KS 67278

PHONE#(316) 685-1441 OPERATORS LICENSE NO. 5131

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-21-89 (date)

by State Plugger, Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4265'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	325'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Circulate heavy mud in hole. 1st plug from 2910' to 2790' w/30 sx. 2nd plug from 2140' to 1740' w/100 sx. 3rd plug from 310' to 110' w/50 sx. Lost returns at 1650', waited 5 1/2 hrs. 4th plug from 40' with wiper plug w/10 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 89

Janek A. Stuck
 Notary Public

My Commission Expires: 12-29-90

