

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
MAY 17 2004
KCC WICHITA

Form CP-4
December 2003
or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Palomino Petroleum, Inc.
Address: 4924 SE 84th Street, Newton, Ks 67114-8827
Phone: (316) 799-1000 Operator License #: 30742
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: May 11, 2004 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 2802' Bottom: 3200' T.D. 3302'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-053-20,617-00-00
Lease Name: Janssen
Well Number: #1
Spot Location (QQQQ): C - E/2 - E/2 - NW
1320' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 29 Twp. 17 S. R. 10 East West
County: Ellsworth
Date Well Completed: N/A 8-14-1980
Plugging Commenced: May 12, 2004
Plugging Completed: May 13, 2004

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	430'	8-5/8"	430'	0'
	Production	0'	3293'	5-1/2"	3293'	1670.09'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Trip in hole with bailer to 3200'. Sand well off to 2750'. Took 70 bbls. of water. Let sand fall. Spot 5 sx cement. M.I.R.U. jacks. Pull slips, broke head off, work and pull stretch. Trip in hole with knife and cut at 1700'. Trip out of hole with knife. Jack out sub and top joint. Pull to 1300'. Copeland pumped 35 sx - 200# hulls. Pulled to 950' - pumped 35 sx. Pulled to 480' - pumped 125 sx and circulated to pit. Pulled rest. Top off with 50 sx. Rigged down jacks, rigged down unit and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525
Name of Party Responsible for Plugging Fees: Palomino Petroleum
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 14th day of May, 20 04
Karen J. Mitchell My Commission Expires: 4/13/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten mark