

RECEIVED

Form CP-4
December 2003

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

MAY 21 2004

Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/27/04 (Date)
by: Rich Williams w/KCC in Hays, KS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3434 Bottom: 3438 T.D. 3490
LKC Depth to Top: 3326 Bottom: 3334 T.D. _____
LKC (continued below) Depth to Top: 3302 Bottom: 3306 T.D. _____

API Number: 15-0711979 / 15-163-20940-00-00
Lease Name: Hrabe A
Well Number: #6
Spot Location (QQQQ): _____ - N2 - SE - SW
990 Feet from North / South Section Line
3300 Feet from East / West Section Line
Sec. 1 Twp. 9 S. R. 17 East West
County: Rooks
Date Well Completed: 07/19/79 9-5-1979
Plugging Commenced: 4/27/04
Plugging Completed: 4/27/04

Show depth and thickness of all water, oil and gas formations. 3296-98, 3282-88, 3219-22, 3173-76, 3155-60

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	204'	8 5/8	204'	0
	Production	Surface	3845' 3488	4 1/2	3845' 3488	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Perf Tech & portable mast. Perforated 4 1/2 csg @ 1725' & 725'. RU Swift Services. Tied onto 8 5/8". Pumped 5 sacks SMD cement.
Pressured to 500# & held. Tied onto 4 1/2" csg. Pumped 175 sacks SMD & 500# hulls. Max pressure 200#. Let set 45 min.
Topped off casing w/10 sacks. Casing stayed full. Plugged @ 2:30 PM. Witnessed by Rich Williams w/KCC in Hays, KS.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tom W. Nichols

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 20th day of May, 2004



Kristin Grady My Commission Expires: 2/06/08
Notary Public



CHARGE TO: *Murphy Drlg. Co.*
 ADDRESS:
 CITY, STATE, ZIP CODE: *Hill City KS*

TICKET No 6444

PAGE 1 OF 1

1. SERVICE LOCATIONS <i>Hays ks</i>	WELL/PROJECT NO. <i>A-6</i>	LEASE <i>Hrabe</i>	COUNTY/PARISH <i>ROOKS</i>	STATE <i>KS</i>	CITY	DATE <i>4-27-04</i>	OWNER <i>Same</i>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO.	SHIPPED VIA <i>105</i>	DELIVERED TO <i>N.E. Plainville</i>	ORDER NO.	
3.	WELL TYPE <i>oil</i>	WELL CATEGORY <i>Abandoned</i>	JOB PURPOSE <i>PTA</i>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
<i>575</i>					<i>MILEAGE 105</i>	<i>35</i>	<i>mi</i>			<i>2.50</i>	<i>87.50</i>
<i>576</i>					<i>Pump charge</i>	<i>1</i>	<i>EA</i>				<i>550.00</i>
<i>275</i>					<i>Hulls</i>	<i>7</i>	<i>SK</i>			<i>20.00</i>	<i>140.00</i>
<i>330</i>					<i>5md Cement</i>	<i>190</i>	<i>SK</i>			<i>10.00</i>	<i>1900.00</i>
<i>581</i>					<i>Bulk service charge</i>	<i>250</i>				<i>1.00</i>	<i>250.00</i>
<i>583</i>					<i>Drayage</i>	<i>435</i>	<i>75</i>	<i>T.M.</i>		<i>.85</i>	<i>370.39</i>
RECEIVED											
MAY 21 2004											
KCC WICHITA											

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

SIGNED *4-27-04* TIME SIGNED *2:00* A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	<i>3297.89</i>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	<i>174.79</i>
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	<i>3472.68</i>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

JOB LOG

SWIFT Services, Inc.

DATE 4-27-04 PAGE NO.

CUSTOMER
Murfin

WELL NO.
A-6

LEASE
Hrabe

JOB TYPE
PTA

TICKET NO.
6444

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1300							on loc
								CIBP 3400
								Ø 4 1/2 CSC
								8 5/8 CSC To 204'
								Prof at 725 + 1275
								old Pufs 3155 - 3400
								hookup to 4 1/2
			69 BBL					Pump 125 SKS SMD CMT w/ 500 # hulls
						200		max PSI 200
								shut in 4 1/2
								Hookup to 8 5/8 Pump 5 SKS cmt
						500		PSI To 500 + held
						500		shut in 8 5/8
			27					Hookup to 4 1/2 Pump 50 SKS SMD
						250		max PSI 250
	1345							wash up TRK + wait on CMT to
								set up in 4 1/2 Top OFF if needed
								Top off 4 1/2 w/ 10 SKS cmt
								4 1/2 185 SKS cmt
								500 # hulls
								8 5/8 5 SKS cmt

WJ

RECEIVED
MAY 21 2004
KCC WICHITA