

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-147-00937-00-80  
 API NUMBER 11-20-57

LEASE NAME Kent  
 WELL NUMBER 2  
 SPOT LOCATION C-NE-NW  
 SEC 22 TWP. 1S RGE. 18 (W)  
 COUNTY Phillips  
 Date Well Completed 11-20-57  
 Plugging Commenced 8-19-85  
 Plugging Completed 8-19-85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Ladd Petroleum Corporation  
 ADDRESS Box 520 Great Bend, Kansas 67530  
 PHONE # (316) 792-3571 OPERATORS LICENSE NO. 6029

Character of Well Input  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation LKC Depth to top 3379 bottom 3336 T.D. 3430

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	205'	None
LKC	Oil & Water	3379	3336	5 1/2	3429'	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 5 1/2 csg mixed 40 sx cement w/5 sx hulls, 40 sx cement w/15 sx gel mud, 110 sx cement, SI Pres. 1500#  
Between 5 1/2 & 8 5/8 csg mixed 75 sx cement, 5 sx hulls, 10 sx gel mud, 75 sx cement, SI Pressure 200#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. \_\_\_\_\_  
 Address Great Bend, Kansas 67530

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

Jerry Rice (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Rice  
 (Address) Box 520 Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3 day of September, 19 85

My Commission expires: \_\_\_\_\_

  
 Ramona L. Dunlap  
 NOTARY PUBLIC  
 State of Kansas  
 EXPIRES 1-23-88

RECEIVED  
 09-04-85  
 SEP 4 1985  
 Form CP-4  
 Revised 01-84