

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-19058-00-01
API NUMBER _____

LEASE NAME Stevens "A"

WELL NUMBER 3

SPOT LOCATION C-NW-NW

SEC. 22 TWP. 1S RGE. 18 (E) (W)

COUNTY Phillips

Date Well Completed 9-22-63

Plugging Commenced 8-19-85

Plugging Completed 8-19-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ladd Petroleum Corporation

ADDRESS Box 520, Great Bend, Kansas 67530

PHONE # (316) 792-3571 OPERATORS LICENSE NO. 6029

Character of Well Input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas District #6

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation LKC Depth to top 3379 bottom 3470 T.D. 3605

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	209	None
LKC	Oil & Water	3379	3470	4 1/2	3583	None

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Down 4 1/2 csg mixed 25 sx cement w/5 sx hulls- 10 sx gel mud w/5 sx hulls, release plug, mixed 100 sx cement w/5 sx hulls, SI Press. 700#
Between 4 1/2 & 8 5/8 csg mixed 75 sx cement w/5 sx hulls, 15 sx gel w/5 sx hulls, 100 sx cement, SI Press. 200#

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allied Cementing Co. License No. _____
Address Great Bend, Kansas 67530

STATE OF _____ COUNTY OF _____, ss.

Jerry Rice (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Rice
Jerry Rice
(Address) Box 520, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 3 day of September, 1985


Ramona L. Dunlap
NOTARY PUBLIC
State of Kansas
MY COMM. EXPIRES 1-23-88

RECEIVED
STATE CORPORATION COMMISSION
Ramona L. Dunlap
Notary Public

My Commission expires: _____

SEP 4 1985
09-04-85
CONSERVATION DIVISION