

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#4
153
API NUMBER 15-220-20,723-00-00

LEASE NAME Heble

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR N-B Company, Inc.

SEC. 35 TWP. 1S RGE. 34 (E/W or W)

ADDRESS P. O. Box 506, Russell, KS 67665-0506

COUNTY Rawlins

PHONE#(913)-483-5345 OPERATORS LICENSE NO. 6111

Date Well Completed 8/5/88

Character of Well D&A

Plugging Commenced 8/5/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/5/88

The plugging proposal was approved on 8-5-88 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4310'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	258'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4310'-2950' 10 sks cement @ 40'
 25 sks cement @ 2950' 15 sks in rathole
 100 sks cement @ 2100' 10 sks in mousehole
 40 sks cement @ 300'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 8241
750

Address P. O. Box 506, Russell, Kansas 67665-0506

STATE OF Kansas COUNTY OF Russell, ss.


Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) P. O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 88

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public



EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

15-15320723-00-00

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, Kansas 67665-0506

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Heble

WELL #1

LOCATION: C NW NW
Section 35-1S-34W
Rawlins County, Kansas

LOGGERS TOTAL DEPTH: 4308'

ROTARY TOTAL DEPTH: 4310'

COMMENCED: 7/27/88

CASING: 8-5/8" @ 258' w/175 sks cement

ELEVATION: 3080' K.B.

COMPLETED: 8/5/88

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil, Sand & Clay	200'	Red Bed	3300'
Shale	2016'	Shale	3814'
Dakota Sand	2127'	Top of Topeka	3815'
Red Bed	2422'	Top of Oread	3947'
Cedar Hills Sand	2469'	Top of Leavenworth	3989'
Red Bed	2932'	R.T.D.	4310'
Anhydrite	2970'		


RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1988

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on August 12, 1988.

My commission expires: February 6, 1992.

GLEND A. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92


Glenda R. Tiffin, Notary Public