

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

15-153-3009
30091-00-00

Rawlins County, Sec. 30 Twp. 1 Rge. (E) 34(W)

Location as "NE/CNW4SW4" or footage from lines C NE SE
Lease Owner Sunray Mid-Continent Oil Company
Lease Name L. Sramek Well No. 1
Office Address P. O. Box 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-7-61 19
Application for plugging filed 3-7-61 19
Application for plugging approved 3-7-61 19
Plugging commenced 3-7-61 19
Plugging completed 3-7-61 19
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	338'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 450'
Set plug at 450' with 20 sacks cement on top of plug
Set plug at 330' with 20 sacks of cement on top of plug
Set plug at 40' with 10 sacks cement on top of plug
Mud to surface

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. R. Nichols (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of March, 19 61

My commission expires 12-24-64 _____ Notary Public.



WELL LOG

15-153-30091-00-00

COMPANY SUNRAY MID-CONTINENT OIL COMPANY

SEC. 30 T. 15 R. 34W

FARM SRAMEK

NO. 1

LOC. C-NE, SE


TOTAL DEPTH 4410'

COUNTY RAWLINS CO, KANSAS

COMM. February 24, 1961 COMP. March 7, 1961

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8 5/8" @ 338' w/225 sax.



ELEVATION 3199' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

175	Top soil & clay
255	Sand
285	Sand & clay
338	Clay
1600	Shale
1865	Chalk & shale
2270	Shale & shells
2385	Shale
2465	Shale & pyrite
2715	Shale & shells
2865	Lime & shale
3000	Shale & shells
3060	Shale & red bed
3095	Stone corral
3233	Red bed
3355	Shale & lime
3485	Shale
3560	Red bed & lime
3680	Lime & shale
3843	Shale, sandy shale & lime
4075	Lime & shale
4410	Kansas City lime.
4410	T. D.

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1961
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 SRAMEK well

Verne A. Morris

Subscribed and sworn to before me this 13th day of March 19 61

My Commission Expires: November 12, 1962

Granfuberg
NOTARY PUBLIC