

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD
15-153-30092-00-00

Sawlin County. Sec. 33 Twp. 1 Rge. 34 (W)

Location as "NE/CNW/SW" or footage from lines C SW 88

Lease Owner Edwin Foster Blair Assoc. & Murfin Drilling Company

Lease Name Trap "B" Well No. 1

Office Address 617 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 7 19 61

Application for plugging filed April 7 19 61

Application for plugging approved April 7 19 61


Plugging commenced April 7 19 61

Plugging completed April 7 19 61

Reason for abandonment of well or producing formation no oil and/or gas found in commercial quantities

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4706 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>8-5/8"</u>	<u>292'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 400'. Set Plug #1 at 400' and 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 290'. Set Plug #2 at 290' and 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #2 to 40'. Set Plug #3 at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
06-06-1961
JUN 6 1961
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Prime Drilling Company
Address 614 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

W. R. Muehl-Patterson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Muehl-Patterson
617 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of April, 19 61

My commission expires June 14, 1964

May Ruedel Blum
Notary Public.

ROTARY DRILLING LOG

15-153-30092-00-00

OPERATOR: Edwin Foster Blair Assoc.
& Murfin Drilling Company
VAP NO. 1
C SW SE Sec. 33-1-34W,
Rawlins County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 3-26-61
COMP: 4-7-61

Surface Casing: Set 8-5/8" surface casing at 292' cemented with 225 sz. Cement.

Formations:

Sand & Clay	50'
Shale	175'
Sand	215'
Shale	1515'
Sand & Shale	1600'
Shale & Shells	2449'
Sand & Shale	2510'
Shale & Shells	2630'
Pyrite & Shale	2710'
Shale & Red Bed	2850'
Red Bed, Shale & Shells	3220'
Lime & Shale	3315'
Shale & Lime	3440'
Lime & Shale	3720'
Lime	3800'
Shale & Lime	3818'
Lime & Shale	4540'
Lime, Shale & Sand	4655'
Lime & Shale	4706'
Rotary Total Depth (D&A)	4706'

RECEIVED
STATE CORPORATION COMMISSION
06-06-1961
JUN 6 1961
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

R. R. Mc Nicol

R. R. Mc Nicol

Subscribed and sworn to before me this 11th day of April, 1961.

Darlene May
Darlene May - Notary Public

My Commission Expires:
September 30, 1963