

15-153-19005-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None
LEASE NAME Cahoj Unit
WELL NUMBER 54
SPOT LOCATION 990' FSL & 990' FE
SEC. 17 TWP. 1 SRGE. 34 (E) or (W)
COUNTY Rawlins
Date Well Completed 4-3-60
Plugging Commenced 3-14-84
Plugging Completed 3-15-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Getty Oil Company
ADDRESS 2705 Vine, Unit #4, Hays, KS 67601
PHONE # (913) 628-1039 OPERATORS LICENSE NO. 6237

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing-KansasCity Depth to top 4068' bottom 4254' T.D. 4263' PBD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KansasCity	Oil	4068'	4254'	8-5/8"	457'	None
				5 1/2"	4305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU Well Service. Ran open-ended tubing to 4253', Spotted 40 sks 50-50 Pozmix w/ 6% gel 4253-3785'. Pulled tubing to 3615'. Tagged cement plug @ 3719' w/ 2" tubing. Spot 80 bbl 9.1 ppg. mud from 479-3713'. Circulated salt water out of 8-5/8" bradenhead & 5 1/2" casing. Spotted 45 sks of 50-50 Pozmix w/ 6% gel from 479' to surface. With 5 sks left to pump, circulated cmt out 5 1/2" csg. Tied onto 8-5/8" surf. pipe & pumped 60 sks 50-50 Poz w/ 6% gel. Circ. 10 sks cmt. out of csg. pit. Well plugged 3-15-84.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287
Address Box 47, Oberlin, KS 67749

RECEIVED
STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Ellis, ss.

Frank Renard (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank Renard

(Address) 2705 Vine, Unit #4, Hays, KS 67601

SWORN TO before me this 4th day of April, 19 84
Bobbie Schippers
Notary Public



My Commission expires: 9-9-84

and witnessed by Carl Goodrow, KCC agent. Cut off casing 6' below ground level and welded steel plate on top of casing. Covered with dirt and leveled location.