

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-153-05237-00-00

API NUMBER \_\_\_\_\_  
 LEASE NAME Cahoj Unit  
 WELL NUMBER 36  
 SPOT LOCATION 2310' FNL & 2310'  
 SEC. 17 TWP. 1S RGE. 34 ~~060~~ or (W) <sup>FWL</sup>  
 COUNTY Rawlins  
 Date Well Completed 1-23-60  
 Plugging Commenced 1-30-84  
 Plugging Completed 3-15-84  
01-31-84

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Getty Oil Company  
 ADDRESS 2705 Vine, Unit #4, Hays, KS 67601

PHONE # (913) 628-1039 OPERATORS LICENSE NO. 6237

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? KCC/KDHE Dist. #6

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing formation L-KC Depth to top 4103 bottom 4246 T.D. 4357

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	Oil	4103	4246	8-5/8	360	None
			0A	5 1/2	4347	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. RIH w/ open-ended tubing. Spotted 40 sks. cement plug (50-50 Poz. w/ 6% gel & 3% CaCl2) 4311-3809'. Filled casing with gelled water 3809-390'. Pulled tubing to 390'. Ran SLM to 3809'. Pumped 35 sks. 50-50 Poz. with 6% gel & 3% CaCl2 from 390' to surface. Pumped 100 sks 50-50 Poz w/ 6% gel & 4 sks hulls down 5 1/2" - 8-5/8" annulus. Pumped @ 2 BPM @ 650#. SI pressure held steady @ 200# Welded steel plate and backfilled & leveled location. Job complete 3-15-84.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287  
 Address Box 47, Oberlin, KS 67749


STATE OF Kansas COUNTY OF Ellis, ss.

Frank Renard (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank Renard

(Address) 2705 Vine, Unit #4, Hays, KS 67601

Subscribed and sworn to before me this 29th day of March, 19 84  
Bobbie Schippers  
 Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 30 1984  
 CONSERVATION DIVISION  
 My appointment expires 3-30-84  
 Wichita, Kansas