

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-153-05297-00-00
API NUMBER 15-4/8/60
LEASE NAME Texaco Cahoj

WELL NUMBER #46
NOTICE: Fill out completely and return to Cons. Div. office within 30 days
2310 Ft. from S Section Line
3630 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 17 TWP1S RGE. 34W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Rawlins
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 4/8/60
Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 3/31/04
Plugging Completed 3/31/04

The plugging proposal was approved on 3/31/04 (date)
by Darrel Dipman w/KCC in Hays, KS (KCC District Agent's Name).
Is ACO-1 filed? No If not, is well log attached? Yes
Producing Formation LKC Depth to Top 4102 Bottom 4188 TD4226 Show depth and thickness of all water oil and gas formations. 4410

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surface	367	8 5/8	367	0
	Production	Surface	4414	5 1/2	4414	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well as follows:

Ran tbg to 2628'. RU Swift. Pumped 130 sxs SMD cmt w/500# hulls. Pulled tbg to 1189'. Pumped 75 sxs SMD w/250# hulls & circ cmt to surface. TOH w/tbg. Hooked up to 8 5/8". Pumped 25 sxs SMD & 50# hulls. Max press 300#. SI @ 200# & held. Hooked up to 5 1/2" csg. Pumped 25 sxs SMD. Max press 400#. Held 200# for 30 mins. SI. Job completed @ 12:30pm. Witnessed & approved by Darrel Dipman w/KCC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202

RECEIVED
APR 29 2004

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

KCC WICHITA

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tom W. Nichols
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 28th day of April, 2004

Notary Public - Kristin Grady

My Commission Expires: 2/06/08 Form CP-4 Revised 05-88

