

15-153-20106-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rawlins County, Sec. 17 Twp. 1 Rge. (E) 34 (W)
Location as "NE/CNW/SW" or footage from lines 150' SE of NW NW
Lease Owner Isern-Wells, Inc.
Lease Name Cahoj Well No. "E" #1
Office Address Box 486, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 7 1971
Application for plugging filed February 7 1971
Application for plugging approved February 7 1971
Plugging commenced February 7 1971
Plugging completed February 7 1971
Reason for abandonment of well or producing formation Dry and abandoned

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clays		0	330	8-5/8"	323'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 2160' cemented w/100 sacks cement.
Filled hole with heavy mud to 340'.
Set 2nd plug @ 340' cemented w/20 sacks cement.
Filled with heavy mud to 40'.
Set 3rd plug @ 40' cemented with 10 sacks cement.
Job completed @ 7:30 P.M. 2-7-71 by Howco.

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1971
CONSERVATION DIVISION
Wichita, Kansas

2-12-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. W. Gabbert (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Gabbert
830 Sutton Place, Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 9th day of February, 1971

Barbara J. Layton
Barbara J. Layton Notary Public.
My Commission expires February 1, 1972



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

15-153-20106-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 12 1971
 CONSERVATION DIVISION
 Wichita, Kansas
 2-12-71

CAHOJ "F" #1
 150' SE of C NW NW Section 17-1S-34W
 Rawlins County, Kansas

Commenced: January 29, 1971
 Completed: February 7, 1971

OPERATOR - Isern-Wells

DEPTH		FORMATION	REMARKS
From	To		
0	40	Clay	Ran 8 joints of 8-5/8" casing, set @ 330' with 260 sacks cement.
40	335	Clay and shale	
335	2434	Shale	
2434	3000	Shale and lime	
3000	3036	Anhydrite	
3036	4270	Lime and shale	
4270	4360	Shale and lime	
4360	TD		Dry and abandoned.

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the 150' SE of C NW NW Section 17-1S-34W, Rawlins County, Kansas to the best of my knowledge and belief.

James S. Sutton, II

 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 10th day of February, 1971, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton

 Barbara J. Layton, Notary Public

My Commission Expires February 1, 1972.

