

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-153-20253-00-00 (of this well) 3/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Beard Oil Company - Gemini Division OPERATORS LICENSE NO. 03317

ADDRESS P.O. Box 309, McCook, NE 69001 PHONE # (308) 345-2480

LEASE (FARM) Cech WELL NO. 1 WELL LOCATION NE NW COUNTY Rawlins

SEC. 27 TWP. 1S RGE. 34 OF (W) TOTAL DEPTH 4326' PLUG BACK TD. 4135'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 240' CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 4330' CEMENTED WITH 200 SACKS

PERFORATED AT 4116'-20'; 4165'-71'; 4215'-20'; 4255'-58'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

See plugging prognosis on back of form.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As soon as approval is received

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

John F. Mondero PHONE # (308) 345-2480

ADDRESS P.O. Box 309, McCook, NE 69001

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. N/A

ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: John F. Mondero

(Operator or Agent)
John F. Mondero

RECEIVED
JUL 10 1987
07-10-1987
STATE CORPORATION COMMISSION
Wichita, Kansas

DATE: 07-07-87

4

BEARD OIL COMPANY
GEMINI DIVISION

1014 WEST THIRD STREET • P.O. BOX 309
McCOOK, NEBRASKA 69001-0309
TELECOPIER NO. 308/345-1381
TELEPHONE 308/345-2480

June 29, 1987

Re: Cech #1
NE NW Sec. 27-T1S-R34W
Rawlins County, Kansas

WELL DATA

4 1/2" 10.5# set at 4330'
T.O.C. 3674'
Perfs. 4116'-20', 4165'-71',
4215'-20', 4255'-58'
CIBP at 4150'
PBD 4135'

PLUGGING PROGNOSIS

1. Move in rig up completion tools.
2. Pressure test tubing to 1500 psi.
3. Lay out rods and tubing.
4. Cover perfs. with 10 sacks 50/50 Pozmix with 2% gel (140').
5. Shoot casing off at free point.
6. Spot 20 sacks at cut off.
7. Spot 10 sacks at 240' (base of surface casing).
8. Fill surface at 40' with 10 sacks.

Should you have any questions or suggestions, please advise.

Yours very truly,

BEARD OIL COMPANY
Gemini Division

John F. Mondero
John F. Mondero
Operations Manager

JFM:lw

State of Kansas



Mike Hayden
Keith R. Henley
Rich Kowalewski
Margalee Wright
Judith A. McConnell

Governor
Chairman
Commissioner
Commissioner
Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

OCT 10 '87

EXPIRES

15-153-20253-00-00

July 10, 1987

WELL PLUGGING NOTICE

Cech #1
NE NW
Sec. 27-01S-34W
Rawlins County

Beard Oil Company
P. O. Box 309
McCook, NE 69001

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Acting Director
State Corporation Commission

Please contact the district office to review your suggested method of plugging

DIST. #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200

five days prior to plugging the well (KAR-82-3-113).