

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-153-05238-00-02

API NUMBER _____

LEASE NAME Cahoj F

WELL NUMBER Cahoj Unit #33
3

4620 Ft. from S Section Line

3150 Ft. from E Section Line

SEC. 17 TWP. 1 RGE. 34 (X) or (W)

COUNTY Rawlins

Date Well Completed _____

Plugging Commenced 8/22/90

Plugging Completed 8/22/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA Operating Co., Inc.

ADDRESS P.O. Box 159, Stafford, Ks. 67578

PHONE#(316) 234 5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-19-90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation KC Lansing Depth to Top 3997 Bottom 4224 T.D. 4297

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface pipe			8 5/8	373	
KC Lansing	Longstring	3997	4224	5 1/2	4297	1200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand back to 3940 w/5 sks common cement on sand w/bailer. Recovered 1220 of 5 1/2 casing w/shot at 2200. Sq 8 5/8 w/200 sks cement blend, followed w/8 sks gel followed w/100 sks cement blend w/500 lbs. hulls mixed into max psi 400 lbs. Close in psi 150 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Chase, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Stafford, ss. 10-10-90

RAMA Operating Co., Inc. (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 159, Stafford, Ks. 67578

SUBSCRIBED AND SWORN TO before me this 5 day of Oct., 19 90

BILLIE POSTIER
Notary Public - State of Kansas
My Comm. Expires Feb. 21, 1992

Billie Postier
Notary Public