

15-153-05291-00-00

SIDE TWO (Page Two)

ACO-1 WELL HISTORY

OPERATOR Getty Oil Company LEASE NAME Cahoj #40 SEC. 16 TWP. 1S RGE. 34W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time lost open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & clay	0	377	Tops	
Shale & sand	377	2140	Fort Hays	1512
Shale & pyrite	2140	3145	Permian	2740
Shale & lime	3145	4364	Stone Corral	2995
			Admire	3679
			Topeka	3854
			Oread	3947
			Lansing	4045
Total Depth	4364			
<p>No DST's.            Ran Schlumberger Induction - Electrical Survey and Microlog to TD. Ran Lane-Well's correlation log to 4340'.</p> <p>Set 8-5/8" casing at 373' w/300 sx.            Set 5-1/2" casing at 4364' w/250 sx.            Perforations: 4282' - 4285', 4289'-4281', 4238'-4245'.            Tested 8 hours for 80.32 B0, no water.</p> <p>Additional perforations after initial completion:            4200'-4202'.            4067'-4072' (later squeezed off).</p>				

STATE OF OREGON  
 RECEIVED  
 OCT 26 1983  
 DEPARTMENT OF REVENUE