

15-039-20127-00-00

CONTRACTOR'S WELL LOG

CONTRACTOR:	Abercrombie Drilling, Inc.
OPERATOR:	A. L. Abercrombie, Inc.
WELL NAME:	HUFF "B" #4 SWD WELL
LOCATION:	100' NE/C SE NE, 8-1S-26W Decatur County, Kansas
SPUD DATE:	October 21, 1969
COMPLETION DATE:	October 22, 1969

0	57	Surface Clay
57	60	Pyrite
60	90	Flint
90	284	Shale
284	925	Shale & Shells
925	1475	Shale & Sand & Gyp
1475	1606	Shale
1606	1708	Sand
1708	1815	Shale
	1815	Rotary Total Depth

Drilled 280' of 12-1/4" surface hole and set 8-5/8" surface csg. @274' w/200 sx. Sunset cement. Cement circulated. Plug was down 5:00 a.m., 10-21-69. Set 5-1/2" csg. @1799' w/350 sx. 50-50 posmix, 6% gel. Plug was down 4:30 p.m., 10-22-69. Completed as a salt water disposal well.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack K. Wharton, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Huff "B" #4 salt water disposal well, located 100' NE/C SE NE, Section 8-1S-26W, Decatur County, Kansas.

Jack K. Wharton

Jack K. Wharton

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, as of this 27th day of October, 1969.

Sue J. Blunck

Sue J. Blunck
Notary Public

My Commission Expires:

July 15, 1972

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1969
CONSERVATION DIVISION
Wichita, Kansas