

To: **6 031412**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-153-05228-00-02
150 E of C 17 1 34
NE NW, SEC. _____, T _____, S, R _____ W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: Rama Operating Co, Inc.
Name & Address Box 159
Stafford, Ks. 67578

4620 feet from S section line
3150 feet from E section line
Lease Name Cahoj F Well # 3
Cahoj Unit 33
County Rawlins 139.65
Well Total Depth 4297 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 373

Abandoned Oil Well Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: PM Day: 22 Month: August Year: 19 90

Plugging proposal received from Millard

(company name) Kelso (phone) _____

were: 8 5/8 set at 373 w/300 sks cwc 5 1/2 set at 4297 w/200 sks. PBDT 4261.
Perfs 3997 - 4224. Order sand and common cmt. Pull pipe. Order 300 sks

65/35 poz 8% gel. 500 lbs. hulls, 8 sks gel, Allied Cement Co. LaRue water trucks.

Ran wireline w/heavy weight through slight bridge at 800.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00PM Day: 22 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3940 w/5 sks common cement on sand w/bailer.

Recovered 1220 of 5 1/2 casing w/shot at 2200. Sq 8 5/8 w/200 sks cement blend,
followed w/8 sks gel followed w/100 sks cement blend w/500 lbs. hulls mixed into
max psi 400 lbs. Close in psi 150 lbs.

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1990
10-03-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

(old, ~~and~~ observe this plugging.

DATE 10-8-90
INV. NO. 29569

[Signature]

Signed Carl Goodrow
(TECHNICIAN)

6 031412

API NUMBER 15-153-05238-00-02

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

150 E of C, SEC. 17, T 1 S, R 34
NE NW
4620 feet from S section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3911
Operator: Rama Operating Co. Inc.
Name & Address: Box 159
Stafford, Ks. 67578

3150 feet from E section line
Lease Name Cahoj F Well # 3
Cahoj Unit 33
County Rawlins
Well Total Depth 4297 feet

Abandoned Oil Well xx ^{wrong} Gas Well _____ Input Well X SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: PM Day: 22 Month: August Year: 19 90
Plugging proposal received from Millard
(company name) Kelso (phone) _____

were: 8 5/8 set at 373 w/300 sks cwc 5 1/2 set at 4297 w/200 sks. PBDT 4261.
Perfs 3997 - 4224. Order sand and common cmt. Pull pipe. Order 300 sks
65/35 poz 8% gel. 500 lbs. hulls, 8 sks gel, Allied Cement Co. LaRue water trucks.
Ran wireline w/heavy weight through slight bridge at 800.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part _____ None _____
Operations Completed: Hour: 1:00PM Day: 22 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3940 w/5 sks common cement on sand w/bailer.

Recovered 1220 of 5 1/2 casing w/shot at 2200 So 8 5/8 w/200 sks cement blend,
followed w/8 sks gel followed w/100 sks cement blend w/500 lbs. hulls mixed into

max psi 400 lbs. Close in psi 150 lbs. Wireline ran to 2200
Location showed last shaving 5 1/2 casing 1220 to
use as a producer 2200 was open

Remarks: D&P D&P
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.
Signed Carl Goodrow (TECHNICIAN)
BEG 2 8 90
12-26-90