

6030119

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-153-05184-00-01  
NE, Sec. 17, T 1 S, R 34 W/E  
990 feet from N/E section line  
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6237

Lease Name Cahoj Unit Well # 31

Operator: Getty Oil Company  
Name & 2705 Vine Street Unit 4  
Address Hays, Kansas 67601

County Rawlins

Well Total Depth 4340 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 446'

141.05

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Oberlin Kansas

Company to plug at: Hour: 5 Day: 26 & 27 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Getty Oil Co. Engineers

(company name) Getty Oil Co. (phone)

were: Pump down 2 3/8 tubing at 4298 with 45 SX 50/50 poz 6%cc gel 3%cc

to 3800' pull tubing to 3800' pump gel to 2790 perforated away. Set easy drill perminate plug through. Pump 100SX. cem. mix. Pull out of plug. Circulate gel to 470' lay down tubing to 470' pump cem. mix to surface. Pump 2SX hulls with 60SX cem. mix. on backside annular space.

Signed Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5 P.M. Day: 27 Month: Jan. Year: 1984

ACTUAL PLUGGING REPORT As Above.

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 2-8-84

INV. NO. 0130

1-27

RECEIVED STATE CORPORATION COMMISSION FEB 06 1984 02-06-84 CONSERVATION DIVISION WICHITA, KANSAS

Signed Carl Goodrow (TECHNICIAN)

FORM CP-2/3 Rev. 9-82