

7-2

4-032244

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-153-20,471 - 00-02

NW SW NE \_\_\_\_\_ /4 SEC. 17, 01, 34 W  
3646 feet from S section line  
2472 feet from E section line

Operator license# 30606 Lease: Cahoj (Texaco) Well # 932  
Operator: Murfin Drilling Company, Inc. County: Rawlins 140.08  
Address: 250 N. Water - Suite #300 Well total depth 4310 feet  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 304 feet

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company License# \_\_\_\_\_

Address: Oakley, Kansas 67748

Company to plug at: Hour: P.M. Day: 2 Month: July Year: 1997

Plugging proposal received from: John Turner

Company: Murfin Drilling Company, Inc. Phone: \_\_\_\_\_

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 15 sxs gel.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
JUL 16 1997  
5:55 AM

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ ], Part[  ], None[ ]

Completed: Hour: 2:10 P.M., Day: 2 Month: July, Year: 1997

Actual plugging report: 8 5/8" set at 304' w/190 sxs cwc. 5 1/2" set at 4304' with 650 sxs. Prod. Perf. 3991' - 4034'. P.B.T.D 4110'. Squeezed 5 1/2" with 50 sxs cement blend with 500# hulls mixed in, followed with 15 sxs gel, followed with 120 sxs cement blend to Max. P.S.I. 1000#. S.I.P. 500#. Held. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 200#. Held. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did[  ] / did not[ ] observe the plugging.

Carl Goodrow  
(agent)

**INVOICED**

DATE JUL 16 1997  
INV. NO. 48550