

Rec'd - KCC-10-29-1987 10-22-87/15153-20075-00-00
6 030982

T&: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NE NW, SEC. 22, T 1 S, R 34 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-153-20015-00-00 4620 feet from S section line
3300 feet from E section line

Operator License # 5988 Lease Name Dozbaba Well # 3

Operator: Halliburton Oil Prod Co. County Rawlins 140.63

Name & Address Box 10 Well Total Depth 4327 feet

Stafford, Kansas 67578 Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 284

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 22 Month: Oct. Year: 19 87

Plugging proposal received from Mark

(company name) Kelso (phone)

were: 10 3/4 set at 284' w/275 sks cwc 7" set at 4326' w/200 sks. D.V. 3054 w/600

Perf 4103' - 4253'. Order sand and Common Cement. Shoot and pull pipe. Order

200 sks Econolite 65/35 Pozmix 10% Gel 2% Dicol. Halliburton Cement Blend. 5 sks

Hulls. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00 PM Day: 22 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4050' w/7 sks Common Cement on sand w/bailer.

Shots at 2100' 1500' 800' 700' 600' 500' 400'. Recovered 400' of 7" casing.

Squeezed 7" and 10 3/4" casing w/200 sks Cement Blend w/5 sks Hulls mixed in.

Max Psi 300# Close in Psi 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

CC. Don B
Bea Stong

DATE 1-6-88
INV. NO. 19372

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

Rec'd
10-29-87

Econolite

$$7'' = 15' / SX$$

$$7\frac{7}{8} \text{ hole } \& \ 8\frac{5}{8} = 10.13' / SX$$

$$5\frac{1}{2} = 26.42 / SX$$

$$4\frac{1}{2} = 40.42 / sh.$$

$$10\frac{3}{4} = 6 / sh. \text{ By Don B.}$$

0316 11

STAO

ON 1961