

6 031024

12-17-87

153-20,386-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

Ne SE, SEC. 21, T 1 S, R 34 W/E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 03317

Lease Name Micek Well # 1 SWD

Operator: Beard Oil Co.

County Rawlins 150.64

Name & Address Box 309

Well Total Depth 4635 feet

McCook, Neb. 69001

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Kansas

Company to plug at: Hour: PM Day: 17 Month: Dec Year: 19 87

Plugging proposal received from John Mondero

(company name) Beard (phone)

were: 8 5/8" set at 293' w/250 sks. 4 1/2" set at 3015' w/750 sks cwc.

Perf. 2929' - 2817'. Improperly plugged Oct. 9, 1987 without notification to state.

Drilled out Dec 17, 1987 and replugged. Order 100 sks Econolite Cement Blend 65/35 Poz 10% Gel 2% Dical Halliburton Cement Co. Water in swab tank.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30PM Day: 17 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Bottom cemented to 2644'. Drilled out 40' of cement on top.

Swabbed 4 1/2" casing dry to 2644'. Loaded 4 1/2" casing with Cement Blend and squeezed to 300# w/app. 85 sks closed in, at 300#. Backside has cement at surface Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
01-18-1988
JAN 18 1988

Remarks: CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 1-20-88

Signed Carl Goodrow (TECHNICIAN)

REV. NO. 19590

Carl Goodrow