

3-15  
4-031895

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-153-20,052-00-00  
150' N. of  
C NE NE /4 SEC. 21, 01 S, 34 W  
4770 feet from S section line  
660 feet from E section line

Operator license# 5988 Lease Micek well # 1

Operator: Halliburton Oil Producing Co. County Rawlins

Address: 525 Central Park Dr. Well total depth 4345 feet 141.21  
Suite #210 Conductor Pipe: 0 inch @ 0 feet  
Oklahoma City, OK 73105 Surface pipe 8 5/8 Inch @ 326 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 15 Month: March Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling Phone: \_\_\_\_\_

Were: Halliburton calculated amount of cementing material and ordered  
210 sxs. 65/35 pozmix - 10% gel - 500# hulls. Ordered sand and common  
cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 4:15P.M., Day: 15, Month: March, Year: 94

Actual plugging report: 8 5/8" set at 326' w/400 sxs. cwc. 4 1/2" set  
at 4344' w/300 sxs. Prod. perms. 4056' - 4255'. Sanded back to 4000'  
w/4 sxs. common cement on sand with bailer. Found out 4 1/2" was top  
staged. Shot at 2800'. Mixed and pumped 160 sxs. cement blend with  
500# hulls mixed in to Max. P.S.I. 100#. Close in P.S.I. 100#.  
Squeezed 8 5/8" with 50 sxs. cement blend to Max. P.S.I. 200#.  
Close in P.S.I. 100#. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC \_\_\_\_\_ , NO \_\_\_\_\_ Dakota plug: YES  NO   
Plugged through TUBING \_\_\_\_\_ , CASING  . Elevation: \_\_\_\_\_  
I did  observe the plugging. Carl Goodrow  
STATE CORPORATION COMMISSION  
MAR 28 1994  
03-26-1994  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**  
DATE 3-30-94  
INV. NO. 40200

(agent)  
Form CP-2/3