



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
02-24-1971  
FEB 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-153-20108-00-00

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Isern-Wells and George Reed,

Complete Address: Box #486, Ellinwood, Kansas.

Lease Name: Dozbaba Well No. 1

Location: 150' NW of CNW-NE Sec. 22 Twp. 1 Rge. (E)(W) 34

County: Rawlins Total Depth 4370' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 260 Sx.  
Top of Dakota section @ 1900'.

Circulate hole with heavy mud. Pull DP to 2175' and displace 100 Sx.  
cement thru DP. Pull DP to 340' and displace 20 Sx. cement thru DP. Pull  
DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

Very truly yours,

*R. L. Nichols*  
Conservation Division Agent