

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water) 212 N. Market
500 Insurance Bldg. WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1969

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clyde Jones of Skelly Oil Company, has this date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: 1860 Lincoln Street, Denver, Colorado.

Lease Name: Frances Horinek Well No. 1

Location: SE-NW-NW Sec. 21 Twp. 1 Rge. (E)(W) 34

County: Rawlins Original RTD- 4953 Total Depth 4293 Oil Well X

Gas Well Dually Completed Oil/SWD Input Well SWD Well D & A Lost Hole

Mr. Jones was instructed to plug the well as follows:

450'--8 5/8" Surface casing, cement circulated.
4827'--5 1/2" Production casing cemented with 300 Sx. Well Plugged back to 4293'. Top perforations @ 4104'.

Push plug to 4000', build bridge and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 40 sacks gel and 85 Sx. cement staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent