

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 5 1973  
12-05-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-153-20174-00-00

Operator's Full Name John O. Farmer, Incorporated.

Complete Address P. O. Box #352, Russell, Kansas.

Lease Name Fikan Well No. 1

Location C SE-NW Sec. 23 Twp. 1 Rge. (E) (W)34

County Rawlins Total Depth 4345'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 6:30 PM Day 1 Month 12 Year 1973

The above well was plugged as follows:

262'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1875'.

Circulated hole with heavy mud. Pulled DP to 2100' and displaced 110 Cu. Ft. cement  
thru DP from 2100' to 1775'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar..

**INVOICED**  
I hereby certify that the above well was plugged as herein stated.

DATE 12/5/73  
INV. NO. 8251-W

Signed: K. L. Dikek  
Well Plugging Supervisor