

KANSAS

al STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-153-20108-00-00

RECEIVED
STATE CORPORATION COMMISSION
02-24-1971
FEB 24 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Isern-Wells and George Reed,
Complete Address Box #486, Ellinwood, Kansas.
Lease Name Dozbaba Well No. 1
Location 150' NW of CNW-NE Sec. 22 Twp. 1 Rge. (E) (W) 34
County Rawlins Total Depth 4370'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones, Incorporated,
Address 830 Sutton Place, Wichita, Kansas. License No.
Operation Completed: Hour 11:30 PM Day 16 Month 2 Year 1971

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 260 Sx.
Top of Dakota @ 1900'.

Circulated hole with heavy mud. Pulled DP to 2160' and displaced 100 Sx. cement thru
DP feom 2160' to 1785'. Pulled DP to 340' and displaced 20 Sx. cement thru DP from
340' to 280'. Pulled DP, set plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Opeho
Well Plugging Supervisor

DATE 2/26/71
INV. NO. 3380-W