

15-153-00034-00-01

Form CP-3  
Rev. 6-26-62

*14*

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1969

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company,

Complete Address: 1860 Lincoln Street, Denver, Colorado.

Lease Name Frances Horinek Well No. 1

Location SE-NW-NW Sec. 21 Twp. 1 Rge. (E) (W) 34

County Rawlins ORIGINAL RTD--- 4953'

Total Depth 4293' Plugging Auth. 4293'  
Abandoned Oil Well  Dually Completed OIL/SWD Gas Well  Input Well  SWD Well  KCC ops 5/25/64  
D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 1:00 PM Day 17 Month 3 Year 1969

The Above well was plugged as follows:

450'--8 5/8" Surface casing, cement circulated.

4827'--5 1/2" Production casing cemented on bottom with 300 Sx. Well plugged back to 4293'. Top perforations @ 4104'.

Pushed plug to 4000', built bridge and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 9 sacks gel and followed with 50 Sx. cement from 1500' to 1300' then 22 sacks gel from 1350' to 475' and followed with 25 Sx. cement from 475' to 400' then 9 sacks gel from 400' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-50#. (Mudding and cementing operations performed by Halliburton). (Rec. 1507' 5 1/2").

I hereby certify that the above well was plugged as herein stated,

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 3/19/69  
INV. NO. 9483-W