

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

FILE RECORDING RECORD
No. R. - 02-3-117

AP. NUMBER 15-153-20386-00-00

LEASE NAME Micek

WELL NUMBER #1

1980 Ft. from E Sect. of

660 Ft. from E Section Line

SEC. 21 TWP. 1S RGE 34 (X) o- (W)

COUNTY Rawlins

Date Well Completed 07-01-80 ^{11-21-80 KCC}

Plugging Commenced 12-17-87

Plugging Completed 12-17-87

LEASE OPERATOR Beard Oil Company

ADDRESS P.O. Box 309, McCook, NE 69001

PHONE# (808) 345-2480 OPERATORS LICENSE NO. 03317

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #4 2301 E. 13th, Hays, KS 67601

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface production				8 5/8"	293'	None
				4 1/2"	3015'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled 4 1/2" casing from PBD 2600'± to surface with 65 sacks (43B) Hays District Light cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. N/A

Address Oberlin, KS 67749

STATE OF Nebraska COUNTY OF Red Willow, ss.

John F. Mondero (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John F. Mondero


(Address) John F. Mondero
Operations Manager
P.O. Box 309, McCook, NE 69001

SUBSCRIBED AND SWORN TO before me this 18th day of December 1987

Kathleen Shaffer Notary Public 12-21-1987

My Commission Expires: 11-21-91

DEC 21 1987



BEARD OIL COMPANY
Micek #21-9
NE SE Section 21-1S-34W
Rawlins County, Kansas

12-18-87

Moved in rigged up completion tools. Rigged up power swivel and pump. Drilled out top plug 8' to 25'. Rigged up and ran blank casing swab. PBTB 2600' \pm . Swabbed well down to PBTB. Rigged up Halliburton. Filled 4 1/2" casing from PBTB to surface with 65 sacks (43 B) Hays District light cement. Job completed at 4:00 PM. Released completion tools. Estimated Cumulative Cost \$1250.

STATE OF KANSAS
DEPARTMENT OF REVENUE
WICHITA, KANSAS

DEC 21 1987

CONSERVATION DIVISION
Wichita, Kansas